

1. FINISH FLOOR
2. FACE OF WALL.
3. 3/4" PARTICLE BOARD (P.BD.) & PLASTIC LAMINATE COUNTERTOP.
4. 3/4" PARTICLE BD. & PLASTIC LAMINATE SPLASH.
5. 3/4" P.BD. @ CABINET.
6. 1/4" BIRCH PLYWOOD BACK (REMOVABLE SECTION) @ BASE CABINET.
7. 3/4" P.BD. BOTTOM @ BASE CABINET - SEE SPECS.
8. 1/4" BIRCH PLYWOOD CABINET BACK.
9. STAINLESS STEEL SINK. SEE PLUMBING DWGS.
10. PRECISION-DRILLED, COMPUTERIZED, 32mm HOLE-BORING SYSTEM. SEE SPECS.
11. CONTINUOUS 3/4" X 4" P.BD. STRETCHER.
12. 3/4" X 4" BIRCH PLYWOOD STIFFENER. FULL LENGTH OF CABINET BACK.
13. 3/4" X 4" CONTINUOUS NAILER, LEVELED @ WALL.
14. ANCHOR NAILER TO WALL @ 24" O.C. MAX., W/ LAG SCREW & WASHER @ WOOD STUDS, OR W/ SHOOT-IN FASTENER AS REQ'D. @ CONC. WALLS, OR W/ TEK SCREWS @ METAL STUDS.
15. SCRIBE PLASTIC LAMINATE TO WALLS, TYPICAL.
16. PROVIDE CONTINUOUS PVC FOAM GASKET @ WALL & CEMENT TO BACK OF SPLASH, TYPICAL.
17. PROVIDE CONTINUOUS ACID-RESISTANT SEALER.
18. ELECTRICAL PLUGMOLD. SEE ELECT. DWGS.
19. UTILITY / SERVICE CHASE AREA.
20. 3/4" P.BD. ADJUSTABLE SHELF W/ MELAMINE SURFACE @ ALL SIDES.
21. 3" X 3/16" LUCITE LIP @ ALL FOUR SIDES OF SHELVING.
22. PROVIDE CONTINUOUS ACID-RESISTANT SEAL & PVC FOAM GASKET @ SPLASH CONNECTION, TYP.
23. PENINSULA / ISLAND CASEWORK UNISTRUT SUPPORT SYSTEM. SEE SPECS. & SHOP DWGS.
24. UNISTRUT CUSTOM ESCUTCHEON PLATE. SEE SHOP DWGS.
25. PENIN. / ISLAND CAB. P-1000 UNISTRUT SUPPORT SYST., AS IN NOTE #23, TO ACCOM. FUT. CASEWK.
26. CABINET, BEYOND.
27. 3/4" P.BD. UPPER-HUNG CABINET. SEE SPECS.
28. 3/4" P.BD. ADJUSTABLE SHELF, W/ MELAMINE SURFACES @ ALL SIDES.
29. ADJ. SHELF RESTRAINING CLIPS PER 32mm HOLE BORING SYSTEM. SEE SPECS.
30. 3/4" P.BD. CABINET DOOR WHERE OCCURS. SEE CASEWK. ELEVS., SCHEDULE, & SPECS.
31. 3/4" P.BD. W/ PLASTIC LAMINATE CAB. DOOR OR FRONT. SEE CASEWK. ELEVS., SCHEDULE, & SPECS.
32. 3/4" P.BD. CABINET BOTTOM. SEE SPECS.
33. RECESSED FLUORESCENT FIXTURE, W/ GLARE REDUCING LENSE. SEE ELECT. DWGS.
34. 3/4" P.BD. UPPER-HUNG CABINET TOP. SEE SPECS.
35. 6" LONG EXTRUDED ALUMINUM CLEAT @ 2'-0" O.C.
36. THRU-BOLT; 3 PER UNIT, TYPICAL.
37. SELF-DRILL & TAP SCREWS FROM HANGER RAIL, 2 PER STUD.
38. SELF-DRILL & TAP SCREWS @ CABINET BACK TO HANGER RAIL. MINIMUM 3 PER UNIT.
39. WOOD BLOCKING @ CABINET BACK.
40. CONTINUOUS EXTRUDED ALUMINUM HANGER RAIL.
41. 1 1/2" X 3 1/2" WOOD SPACER. HOLD BACK 1" FROM CAB. ENDS, & PAINT EXPOSED SURFACES.
42. 1/4" X 3" TEK SELF-TAPPING SCREWS W/ WASHERS. PROVIDE MINIMUM 2 PER CABINET.
43. 3" X 3/16" LUCITE LIP.
44. 3/4" P.BD. SOFFIT AREA TO RECEIVE FLUORESCENT TASK LIGHT.

CASEWORK DETAIL NOTES

FULL SCALE

A771-0

ARCHITECTURAL STANDARD DETAILS
CASEWORK NOTES

DRAWN BY W.C.	DETAIL TYPE CASEWORK
DATE 7/6/98	SCALE FULL SIZE
APPROVED BY	SHEET
DATE	A771-0
DRAWING FILE NAME A771-0.DWG	1

UNIVERSITY OF CALIFORNIA - LAWRENCE BERKELEY NATIONAL LABORATORY
FACILITIES DIVISION