EQUIPMENT AND FURNITURE SCHEDULE

EQUIPMENT NO.	EQUIPMENT ITEM :	MANUFACTURER	MODEL / NO.	EQUIP. DIMENSIONS (IN INCHES) W	D	H	WT	ELECTRICAL LOAD VOLTS	PHASE	KW	HP	AMPS	COMP. AIR CONN.	RATE	PRESS.	WATER CONN.	RATE	PRESS.	VACUUM CONN.	RATE	PRESS.	REMARKS
1	COMPRESSOR	GARDNER DEUER	3057	24	40	48	1000	220/440	3	4.5	7.5	21/10.5										
2	COMPRESSOR	GARDNER DEUER	3038	24	40	48	1000	220/440	3	6	10	27/13										
3	PUMP	GOULDS	3196	12	42	30	400	115/230	1	1.6	1	3.5/7										
4	COOLER			36	36	60	300	220	1	1.3												
5	VACUUM PUMP	CENCO	91705	24	12	18	100	110	1	1	0.5	8							24	24	24	
6	EQUIPMENT RACK	LBL	–	45	24	80	300	110	1	1	–	10										
7	PULSER	COBER	605P	20	22	15	200	110	1	0.5	–	5										
8	COMPUTER	IBM	AT	24	20	20	50	110	1	0.5	–	3										
9	PRINTER	QMS	PS410	16	14	8	25	110	1	0.2	–	2										
10	OSCILLOSCOPE	LE CROY	9424B	14	20	8	50	110	1	0.2	–	2										
11	COMPUTER	APPLE	IIC1	24	24	24	50	110	1	0.2	–	2										
12	BALANCE	SHIMADZA	A2L	40	40	40	300	110	1	0.1	–	1										
13	OVEN	GRIEVE	RW8270	24	24	34	200	110	1	0.5	–	5										
14	OVEN	ASSOCIATED		38	24	34	200	220	2	1	–	10										
15	OVEN	LAB LINE	3500	20	20	26	75	110	1	0.1	–	1										
16	LOAD FRAME	LBL	–	123	23	100	5000	110	1	2	–	20	1/2	1 SCFM	90 PSIG	1/4	.1 SCFM	24				
17	LOAD FRAME	LBL	–	36	43	80	500	110	1	2	–	20										
18	COMPUTER	IBM	AT	24	20	20	50	110	1	0.5	–	3										
19	PULSER	COBER	605P	20	22	15	200	110	1	1.5	–	17										
20	VACUUM PUMP	WELCH	1402	12	18	22	100	110	1	1.5	1	13.6										
21	POWER SUPPLY	VALIDYNE	MC1333	10	10	15	20	110	1	0.1	–	1										
22	COMPUTER	H.P.	85	15	15	5	20	110	1	0.1	–	1										
23	HIGH PRESSURE CELL																					
24	PERMEAMETER STAND																					
25	GAMMA RAY EXPERIMENT																					
26	GLOVE BOX																					
27	DESK																					
28	DESK																					
29	ROLLING COMPUTER TABLE																					
30	COMPRESSED GAS CYLINDERS																					
31	LIQUID NITROGEN TANK																					
32	WORK TABLE																					
33	WORK TABLE																					
34	WORK TABLE																					
35	SMALL TABLE																					
36	SMALL TABLE																					
37	TOOL CHEST																					
38	STORAGE CABINET																					
39	STORAGE CABINET																					
40	STEEL SHELVING UNIT																					
41	5 DRAWER FILE UNIT																					
42	CASEWORK																					
43	CASEWORK																					
44	CASEWORK W/ SINK																					
45	WORK TABLE																					
46																						
47																						
48																						
49																						
50																						

(ONE–HALF–FULL SCALE)

ARCHITECTURAL STANDARD DETAIL

EQUIPMENT SCHEDULE

UNIVERSITY OF CALIFORNIA – LAWRENCE BERKELEY NATIONAL LABORATORY

FACILITIES DEPARTMENT

DRAWN BY	DETAIL TYPE SCHEDULES
DATE 00/00/00	SCALE NOTED
APPROVED BY	SHEET A803
DATE	
DRAWING FILE NAME A803	