

ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME :	FLOOR	BASE	WALLS				CLGS.	REMARKS :
				N	E	S	W		
240	COMMON AREA	F5	B1	W1 W2	W1	W1	W1	C7	
240A	OFFICE	F5	B1	W1 W2	W1	W1	W1	C7	
240B	OFFICE	F5	B1	W1	W1	W1	W1	C7	
240C	OFFICE	F5	B1	W1	W1	W1	W1	C7	
240D	STORAGE	F5	B1	W1	W1	W1	W1	C7	
241	LAB/SEMI-CLEAN RM.	F1	B1	W1	W1	W1	W1	C1	
243	OFFICE	F5	B1	W1	W1	W1	W1	C7	
245	OFFICE	F5	B1	W1	W1	W1	W1	C7	
247	COPY ROOM	F1	B1	W1	W1	W1	W1	C7	
288	CORRIDOR	F1	B1	W1	W1	W1	W1	C4	1 HR. FIRE RATED CEILING.
289	CORRIDOR	F1	B1	W1	W1	W1	W1	C4	1 HR. FIRE RATED CEILING.
297	CORRIDOR (E)	F4	B4	W5	W5	W4	W5	C3	(N) FLOOR & WALL FINISH ADJACENT TO DOOR #20, ONLY.

ROOM FINISH LEGEND:

FLOORING:

- "F1" (N) VINYL TILE (VCT "A" OR AS INDICATED)
- "F2" (N) SHEET VINYL FLOORING.
- "F3" (N) SHEET VINYL OVER (E) CERAMIC TILE.
- "F4" (E) FLOORING TO REMAIN.
- "F5" (N) CARPET.

WALLS:

- "W1" (N) PAINTED GYP. BD.
- "W2" (N) PAINTED GYP. BD FURRING.
- "W3" (E) WALL TO REMAIN. PATCH ALL HOLES PER W4.
- "W4" PATCH AND RE-FINISH (E) WALL. PAINT TOP COAT ONLY @ (E) INTACT SURFACES; 3 COATS @ (N) WORK.
- "W5" (E) TO REMAIN.

BASE:

- "B1" (N) TOP SET RUBBER BASE.
- "B2" NOT USED
- "B3" (N) INTEGRAL COVED BASE, 6" TYP.
- "B4" (N) BASE AT (N) WALLS ONLY.
- "B5" (E) BASE TO REMAIN.

CEILING:

- "C1" (N) SUSPENDED CLEAN ROOM CEILING.
- "C2" PATCH & REPAIR (E) CEILING.
- "C3" (E) CEILING TO REMAIN.
- "C4" (N) PAINTED GYPSUM BOARD CEILING.
- "C5" (N) FURRED GYPSUM BOARD.
- "C6" (N) GYP. BD CEILING OVER EXISTING TILE.
- "C7" (N) SUSPENDED ACOUSTICAL PANEL CEILING
- "C8" PATCH GYP. BD. AND (N) GYP. BD. ON (E) GYP. BD.
- "C9" (N) ACOUSTICAL TILE OVER (N) GYP. BD. SCREWED TO METAL FURRING CHANNELS ATTACHED TO BOTTOM OF STEEL DECKING.

(95%-FULL SCALE)

ARCHITECTURAL STANDARD DETAIL ROOM FINISH SCHEDULE

UNIVERSITY OF CALIFORNIA – LAWRENCE BERKELEY NATIONAL LABORATORY
FACILITIES DEPARTMENT

DRAWN BY	DETAIL TYPE
DATE 00/00/00	SCALE NOTED
APPROVED BY	SHEET
DATE	A805
DRAWING FILE NAME A805	